

TRICOUNTY LINK SITE IMPROVEMENTS
TOWN OF MONCK'S CORNER, SC
Unit Prices -

ITEM #	ITEM/DESCRIPTION	UNIT OF MEASURE	QUANTITY	MATERIAL PRICE	<i>Include Sub Work</i>		TOTAL UNIT PRICE
					LABOR PRICE		
	DEMOLITION & EROSION CONTROL						
1	Mobilization/Demobilization	LS	1				
2	Erosion Control Measures (Sediment Tubes, etc.)	LS	1				
3	Demolition and Disposal of Existing Concrete Pavement	SF	10,687				
4	Removal and Reuse/Spreading of Rock/Gravel Pavement	SF	6,721				
5	Removal and Disposal of Ex. Chain Link Fence (Back Area)	LF	244				
6	Removal and Disposal of Ex. 8" Drain Pipe under Metts Street Entrance	LS	1				
7	Saw Cut of existing Concrete Edges for smooth transition	LS	1				
8	Removal of existing Bollard, sign and brick pavers at building entrance	LS	1				
9	Soil Stabilization (grassing disturbed area without concrete pavement)	LS	1				
	PAVEMENT AND DRAINAGE SYSTEM						
10	Prepare, Compact and Grade Subgrade for Concrete Pavement	SY	1,828				
11	Concrete Pavement (per pavement section on Sheet C5.00)	SY	1,828				
12	Wheel Stops	EA.	66				
13	Bollards	EA.	14				
14	ADA Signs	EA.	5				
15	ADA symbols & Stripping	LS	1				
16	Stop Sign	EA.	1				
17	Trench Drain (per detail on sheet C6.00)	LF	182.5				
18	Traffic Rated ADS Gate	EA.	1				
19	Non Traffic Rated ADS Gate	EA.	1				
20	10" HDPE Pipe	LF	39.5				
21	Connect proposed 8" HDPE to existing grate inlet at Metts Street	EA.	1				
22	Connect proposed trench drain to existing grate inlet at the back area	EA.	1				
23	Regrading of gravel adjacent to the proposed trench drain	SY	50				
24	Regrading of gravel at the washed-out area located Southwest of the building	SY	20				
25	Regrading of gravel at the entrances along Metts Street	SY	30				
	FENCING						
26	Chain Link Fence	LF	244				
27	Decorative Fencing along Heatley and Gulledege Street	Panel	3				
			<i>Total</i>				